

2699 East CR 50 Tiffin. OH 44883 Tiffin Office: 419-618-3072 Fax: 419-443-0539 Huntsville Office: 937-539-0094 Fax 937-843-3079

hhenvironmental@yahoo.com



Asbestos Survey

2199 Co. Rd. 8; West Mansfield, OH 43358

LUC Regional Planning Commission



2699 East CR 50 Tiffin. OH 44883 Tiffin Office: 419-618-3072 Fax: 419-443-0539 Huntsville Office: 937-539-0094 Fax 937-843-3079 hhenvironmental@yahoo.com

LUC Regional Planning Commision

10/31/23

10820 SR 347

East Liberty, OH 43319

Phone:937-666-3431

Email: heathermartin@lucplanning.com

Heather Martin

Asbestos survey: 2199 Co Rd. 8; West Mansfield, OH 43358

Heather,

H&H Environmental, LLC. has completed an inspection for asbestos-containing materials (ACM) at 2199 Co Rd. 8; West Mansfield, OH 43358. This inspection was performed by Tyler Rister (Certification # 35958) and Jace Hurt (Certification # 36450) on October 25th, 2023 in West Mansfield, OH. Tyler Rister and Jace Hurt maintain a current Ohio EPA Asbestos Inspector Certifications. Proof of these certifications are attached.

Enclosed:

- 1. Asbestos Survey Cover
- 2. Asbestos Survey Letter
- 3. Purpose and Procedure
- 4. ACM Summary and Notice
- 5. Sample Chain-of-custody
- 6. Sample Site Pictures
- 7. Laboratory Analysis Report (and point-count analysis if applicable)
- 8. Asbestos Inspector Certifications

Purpose of Inspection:

The ACM inspection was conducted in accordance and observation of EPA NESHAP and OSHA regulations pertaining to the demolition/renovation of regulated structures. This inspection included all applicable and accessible areas of the structure.

Procedure:

The inspection, conducted on 10-25-2023, was completed utilizing applicable Federal and Ohio State regulations pertaining to asbestos: Federal OSHA (29 CFR 1910.1001and 29 CFR 1926.1101), EPA (40 CFR Part 61), and TSCA Title II AHERA/ASHARA (40 CFR Part 763) Asbestos Regulations. The findings in this report are consistent with accepted principles and practice established and prescribed by the EPA and AHERA.

All accessible areas of the building in West Mansfield, OH were inspected physically, functional space by functional space, and homogeneous area by homogeneous area to determine the presence of asbestos-containing materials. Suspected asbestos-containing materials were grouped per homogeneous area. Suspect materials that may be present inside wall cavities, electrical wiring or which were otherwise inaccessible were not included in the scope of this inspection. Core samples of friable and non-friable suspect asbestos-containing materials were collected to be analyzed for asbestos content. Those materials considered to be non-suspect (concrete, wood, fiberglass, carpeting, metal, etc.) were not sampled for analysis. Each location for sample collection, chosen at random, were representative of the suspect materials. The bulk samples were placed in zip-lock bags, sealed, and labeled with an identifying code. The samples, along with the chain-of-custody, were then submitted to the laboratory, McCall and Spero Environmental, Inc., to be analyzed for asbestos content. A copy of the chain-of-custody is attached.

12 bulk samples of suspected ACM, were submitted to a laboratory for analysis using Polarized Light Microscopy. Laboratory results are attached.

Analytical Results:

H&H Sample #	Homogenous	Layers	Description/	PLM Result
Lab Sample #	Area		Sample Location	
2199-01	1	2	Plaster Rm.8 Wall A	15% Chrysotile
PO263HHE.4-01				
2199-02	1	2	Plaster Rm.6 Wall D	ND
PO263HHE.4-02				
2199-03	1	2	Plaster Rm.7 Wall D	ND
PO263HHE.4-03				
2199-04	1	2	Plaster Stairs Wall C	ND
PO263HHE.4-04				
2199-05	1	2	Plaster Rm.4 Wall A	ND
PO263HHE.4-05				
2199-06	1	2	Plaster Rm.2 Wall C	ND
PO263HHE.4-06				
2199-07	1	2	Plaster Rm.1 Wall C	ND
PO263HHE.4-07				
2199-08	2	1	Window Glaze Rm.2 Wall	4% Chrysotile
PO263HHE.4-08			C	
2199-09	2	1	Window Glaze porch Wall	4% Chrysotile
PO263HHE.4-09			D	
2199-10	3	1	Transite siding outside	15% Chrysotile
PO263HHE.4-10			Rm.2	
2199-11	4	1	Asphalt Roofing debris	ND

PO263HHE.4-11	outside Rm. 1&2	
2199-12 4 PO263HHE.4-12	Asphalt Roof debris outside Rm.5	ND

Summary:

Based the analysis of suspected ACM samples, a number of the samples of homogenous areas were determined to be asbestos-containing.

The approximate total of asbestos-containing materials are as follows:

Transite Siding 2,400 Sq.ft.

Wooden Window Glaze 9 Windows

Among the material noted above, the <u>Transite siding and Window Glazing</u> material must be removed by a licensed asbestos abatement contractor prior to renovation or demolition if it would impact this material.

Under current Ohio standards materials containing less than 1% are not "asbestos containing material". However, this material is still regulated under OSHA and must adhere to wet handling, prompt cleanup, disposal requirements set forth by 29 CFR 1926 as applies to demolition operations involving materials containing less than 1% asbestos.

Notice:

An Ohio EPA Notification of Demolition and Renovation form must be completed and submitted to the Ohio EPA at least ten working days prior to the commencement of any abatement or demolition activity. The amount, type and condition of the asbestos-containing materials found in this inspection, as well as the materials assumed to be asbestos-containing materials, must be noted on the form. The name and certification number of the asbestos inspector must be included.

If any additional materials are encountered in these locations, these materials should be left intact and undisturbed until they can be inspected and and sampled by a licensed Asbestos Abatement Evaluation Specialist. H&H Environmental would be happy to return to the site if additional

suspect materials are encountered during demolition activity. The other option is to assume that the material is asbestos-containing and have it abated as such.

This report, and the supporting findings, data, conclusions, and recommendations represents H&H Environmental's efforts on behalf of the client. This report is not an asbestos abatement specification and shouldn't be used for specifying removal techniques or methods. The assessments, conclusions, results, and recommendations stated in this report are representative of the circumstances and conditions observed by the inspector at the date of the inspection. We cannot assume responsibility for any change in conditions or circumstances that occurred after inspection. The findings in this report, if implemented by the client, should not be construed as as an assurance or implied warranty for the continuing safety, performance, or cost-effectiveness of any equipment, system, product, procedure, facility, or policy recommended or discussed herein.

The recommendations in this report are based on the professional judgment of the inspector and the results of the samples collected an analyzed. H&H Environmental makes no warranty, expressed or implied, and accepts no liability for the presence or absence of asbestos or other hazardous materials in or on home products, materials, and areas. H&H Environmental assumes no responsibility for the cost of repairing, removing, or replacing any undiscovered or unreported condition or defect, or any future condition or defect.

If you have any questions or concerns please feel free to contact H&H Environmental's Charles E. Hurt at 419-618-3072.

Thank you,

Tyler Rister

AHES # ES 35958

H&H Environmental


Jace Hurt Just


AHES # ES 36450

H&H Environmental

H&H Environmental	Asbestos Inspection Work S	heet
Site 2/99 6.181 8 C	City West Martiled State 14 Zip 4339	
Kenovation_	Demolition	
Levels: 1 2 3 Attic	Foundation: Slab Crawl Basement	
Exterior: Wood Vinyl Aluminum _	Asphalt Transite Brick Block	
Interior Walls: Drywall Plaster Pan	eling Transite Other	
Windows: Wood Vinyl Metal (Other Number	
Flooring: Wood Concrete 9" Tile	12" Tile Linoleum Ceramic	
Heating: FAF Hot Water Furnace Bo	pard Duct Work Seam Tape Duct Boots	
Roofing: Asphalt / Metal Transite	Build Up Other	
A 1st Floor	A 2nd Floor	
	,	
14' /	B'	
	(2)	
	12. 0 13.	
16	(a) 10 (b)	
C Z 16 11 3	10° 7 10° 8	
(O) (i) provided the control of the	Stehro	
(4) B	D	3
w@		ř.
<i>y y</i>		
18 10		
m S r		
2 6		
N 8 15.		
W @W		
C	C	
Ceiling Height	Ceiling Height 8 5	
A Basement	A	
B		
В	0	
6		
	c	
annoctor III I D'		
nspectorTyler Rister	Certification # ES35958 Date 10/cs/23	

	Material	Room Location	Color	Condition	Quantity
<u>t/</u>	Plaster	Throughost	NA	GIF	4.800 56
	Window Galage	7,5, Perch, 4	white	GIF	9 Windows
3	Wind) Transle Siding	5. drug	white	GIF	2,400 51
4	Asphalt Roofing	Robing		F	1,500 SF
					•
				+	
······································					
f	To Com Peman 1	e dem			
Good S:	F = Fair P = Poor FR =	Friable NF = Non Friate Sound house x Wood A House full of Was agrees found	sie Shingles or frans frans frans frans frans	Building Clear The It Ray Let Higher The Vise I	New to 2nd








































































Specialists in Microanalysis

E-mail: customerservice@mselabs.com • Website: www.mselabs.com

Date: October 26, 2023

Attention: Chuck Hurt

H & H Environmental

Subject: Analysis of bulk samples for asbestos mineral fibers by Polarized Light

Microscopy (PLM) with Dispersion Staining (EPA/600/R-93/116)

RE: MSE-PO263HHE.4

2199 Co Rd. 8; West Mansfield, OH 43358 Project

Dear Mr. Hurt:

McCall & Spero Environmental, Inc. has completed the analysis of the bulk samples we received from your offices on October 26, 2023. These samples represent the bulk samples from the 2199 Co Rd. 8; West Mansfield, OH 43358 Project.

The PLM bulk analysis was performed according to the "Method of the Determination of Asbestos in Bulk Building Materials", R. L. Perkins and B. W. Harvey (EPA/600/R-93/116).

The results for the nineteen (19) samples are summarized in the following report. Please note that for samples consisting of two or more distinct components, each component is analyzed and reported individually (EPA 40 CFR Part 61 [FRL-4821-71]).

Thank you for consulting McCall & Spero Environmental, Inc. Should you have any questions concerning these results, please contact our office.

Sincerely,

Kevin R. Bean, B.A. PLM Laboratory Director



SUMMARY OF PLM BULK ANALYSIS RESULTS

Page 1

Project Name: 2199 Co Rd. 8; West Mansfield, OH 43358 Project McCall & Spero Environmental Project No. MSE-PO263HHE.4

MSE # PO263HHE.4	SAMPLE # DESCRIPTION	ASBESTOS TYPE & %	OTHER FIBROUS MATERIAL & %	% NON-FIBROUS MATERIAL	COLOR
001 (A)	2199-01 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
001 (B)	2199-01 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
002 (A)	2199-02 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
002 (B)	2199-02 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
003 (A)	2199-03 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
003 (B)	2199-03 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
004 (A)	2199-04 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
004 (B)	2199-04 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
005 (A)	2199-05 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
005 (B)	2199-05 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
006 (A)	2199-06 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
006 (B)	2199-06 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
007 (A)	2199-07 (A) Skim Coat	ND**	Cellulose / 2%	98%	White
007 (B)	2199-07 (B) Plaster	ND**	Cellulose / 7% Hair / 3%	90%	Gray
008	2199-08 Window Glaze	CH / 4%	Cellulose / 2%	94%	White

McCall & Spero Environmental, Inc.

SUMMARY OF PLM BULK ANALYSIS RESULTS

Page 2

MSE # PO263HHE.4	SAMPLE # DESCRIPTION	ASBESTOS TYPE & %	OTHER FIBROUS MATERIAL & %	% NON-FIBROUS MATERIAL	COLOR
009	2199-09 Window Glaze	CH / 4%	Cellulose / 2%	94%	White
010	2199-10 Transite Siding	CH / 15%	ND	85%	Gray
011	2199-11 Asphalt Roof	ND**	Cellulose / 30%	70%	Black
012	2199-12 Asphalt Roof	ND**	Cellulose / 30%	70%	Black

NOTES:

ND = None Detected

CH = Chrysotile

A = Amosite

AC = Actinolite

CR = Crocidolite

AN = Anthophyllite TR = Tremolite

For samples consisting of separate components, each component is analyzed and reported separately.

Results apply only to items tested. Quantification is accurate to within \pm 10%. Results from this report must not be reproduced, except in full, with the approval of McCall & Spero Environmental, Inc. This report must not be used to claim product endorsement by NVLAP or any agency of the U.S. Government.

** EPA recommends that bulk materials found negative for asbestos or less than one percent asbestos by polarized light microscopy that fall into one of five dominantly nonfriable categories be reanalyzed by an additional method, such as transmission electron microscopy. (EPA Notice of Advisory, FR Vol. 59, No. 146 & Test Method EPA 600/ R-93/116).

Analyst: Kevin R. Bean, B.A.



1831 Williamson Court • Suite 100 • Louisville, KY 40223 Phone (502) 244-7135 • (800) 841-0180 • FAX (502) 244-7136

E-mail: customerservice@mselabs.com • Website: www.mselabs.com

BULK SAMPLE CHAIN OF CUSTODY FORM

Company:	H&H Environmental Telephone #	419-618-3072 Fax#: 419-443-0	539
Contact:	Chuck Hurt :	Client Project Number:	
Relinquished b	y: Tyler Rister	Date: /9/25/23 Time://	20
Written Repor	t To: _lke Hurt		
Project Name:	2199 C. Rol & West M	Martald OH 43358	
Turn-Around (Circle One): Same Day 24 Hour 2-3 I	Day 4-5 Day Weekend Rush A	fter Hour Rush
Analysis Reque	ested (Circle One): PLM Bulk Analysis 7	TEM Qualitative Analysis TEM Quantitative Ar	alysis (4-5 Day)
For Laboratory	Use Only		
MSE Project#	100263HHE.4	Method: EPA/600/R-93/116	
Samples Receiv	red by: 2 2 3	Date: 10/26/23 Time: 1	21-

Client Sample Number	Location	Sample Description	Sampled By
2199-01	Plaster from 8 wall A		
2199-02	Plaster from 6 WAND		
2199-03	Plaster form 7 Well O		
7199-04	Planter States Well C		
2199.05	Plaster from y well A		-
2199-06	Planter from 2 Well C		
2199-07	Plaster form I wall C		
2199-08	Window Glass Loom 2 WE	4 6	
2199-09	Window Glaze Porch Wall	n	
			,
2199-10	floorite girling outside from	2	
	, ,		
2199-11	Asphilt Roof dibris outsid	1/2	
2199-12	Asohalt Rust debris outsoh	lam 5	
			•
		0	



Asbestos Building Inspector Refresher

Certificate

This is to certify

Tyler Rister

XXX-XX-1478



section 855.120 of Title 77. IDPH recognition based on student request. Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763 has attended and successfully completed the Asbestos Hazard Emergency Response Act mandatory course for the Asbestos Building Inspector Indiana requirements under 326 IAC 18-2 and Chapter 3745-22 Ohio Administrative Code, and the Illinois Department of Public Health (IDPH) under (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act and State of

Course Location	Examination Date	Date(s) of Course	Expiration Date	Training Manager
Columbus, OH	11/30/2022	11/30/22	11/30/23	Less St.

33150 Lakeland Blvd. Cleveland, OH 44095 www.TSltraining.com

Course Certificate No.

22 TSI 418145 ir

5

TRAINING SERVICES INTERNATIONAL

Asbestos Management Planner Refresher

Certificate

Thus is to certify

Tyler Rister

XXX-XX-1478



has attended and successfully completed the Asbestos Hazard Emergency Response Act mandatory course for the Asbestos Management Planner Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763 section 855.120 of Title 77. IDPH recognition based on student request. Indiana requirements under 326 IAC 18-2 and Chapter 3745-22 Ohio Administrative Code, and the Illinois Department of Public Health (IDPH) under (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act and State of

Course Location	Examination Date	Date(s) of Course	Expiration Date	Training Manager
Columbus, OH	11/30/2022	11/30/22	11/30/23	As Cal

33150 Lakeland Blvd. Cleveland, OH 44095 www.TStraining.com

Course Certificate No. 2

22 TSI 418151 mpr



Asbestos Contractor Supervisor Refresher

Certificate

This is to certify

Tyler Rister

XXX-XX-1478



has attended and successfully completed the Asbestos Hazard Emergency Response Act mandatory course for the Asbestos Contractor Supervisor section 855.120 of Title 77. IDPH recognition based on student request Indiana requirements under 326 IAC 18-2, Chapter 3745-22 Ohio Administrative Code, and the Illinois Department of Public Health (IDPH) under (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act, State of Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763

Training Manager

11/29/23 Expiration Date

11/29/22
Date(s) of Course

11/29/2022

Examination Date

Course Location

Columbus, OH

33150 Lakeland Blvd. Cleveland, OH 44095 www.TSltraining.com

Course Certificare No.

22 TSI 418032 csr



Asbestos Building Inspector Refresher

Certificate

This is to certify

lace Hurt

XXX-XX-0133



section 855.120 of Title 77. IDPH recognition based on student request. (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act and State of Indiana requirements under 326 IAC 18-2 and Chapter 3745-22 Ohio Administrative Code. and the Illinois Department of Public Health (IDPH) under Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763 has attended and successfully completed the Asbestos Hazard Emergency Response Act mandatory course for the Asbestos Building Inspector

-	1
	9
	1
-	1
1	
1	30
1	
1	

11/30/23

11/30/22

11/30/2022

Columbus, OH

33150 Lakeland Blvd Training Manager

www.TSltraining.com Cleveland, OH 44095

Expiration Date

Date(s) of Course

Examination Date

Course Location

Course Certificate No.

22 TSI 418147 ir



Asbestos Management Planner Refresher

Certificate

This is to certify

Jace Hurt

XXX-XX-0133



Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763 (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act and State of Indiana requirements under 326 IAC 18-2 and Chapter 3745-22 Ohio Administrative Code, and the Illinois Department of Public Health (IDPH) under section 855.120 of Title 77. IDPH recognition based on student request. has attended and successfully completed the Asbestos Hazard Emergency Response Act mandatory course for the Asbestos Management Planner

Course Location	Examination Date	Date(s) of Course	Expiration Date	rairing Manager
				T 76
Columbus, OH	11/30/2022	11/30/22	11/30/23	Less Color

33150 Lakeland Blvd. Cleveland, OH 44095 www.TSltraining.com

Course Certificate No.

22 TSI 418153 mpr



Asbestos Contractor Supervisor Refresher

Certificate

This is to certify

Jace Hurt

XXX-XX-0133



has attended and successfully completed the Asbestos Hazard Ernergency Response Act mandatory course for the Asbestos Contractor Supervisor section 855.120 of Title 77. IDPH recognition based on student request. Refresher and has passed an examination in that course with a minimum score of 70% or better. Training was in accordance with 40 CFR Part 763 Indiana requirements under 326 IAC 18-2, Chapter 3745-22 Ohio Administrative Code, and the Illinois Department of Public Health (IDPH) under (AHERA). The above student received the requisite training for asbestos accreditation under Title II of the Toxic Substances Control Act, State of

Train	1
ing Manager	KL
Expiration Date	11/29/23
Date(s) of Course	11/29/22
Examination Date	11/29/2022
Course Location	Columbus, OH

33150 Lakeland Blvd. Cleveland, OH 44095 vwww.TSltraining.com

Course Certificate No.

22 TSI 418034 csr